


SITE DEVELOPMENT DATA - COMPREHENSIVE TRANSPORTATION REVIEW SUMMARY			
Proposed Trip Generation			
Land Uses	Density	Daily Trips/Peak Hour Trips	
1) Multi-Family (Mid-Rise) Housing [221]	14.2	801 Daily/ 68 AM/ 68 PM	
2)			
3)			
4)			
5)			
Total:		801 Daily/ 68 AM/ 68 PM	
Multimodal Mitigation		Tier: 1	
		Required Points: 3	
List of Mitigations: TBD			
1) 816 LF Shared-Use Path along Mount Holly Road = 16 points			
2)			
3)			
4)			
5)			
Transportation Demand Management Mitigation		Tier: N/A	
		Required Points: N/A	
List of Mitigations: N/A			
1)			
2)			
3)			
4)			
5)			
TIS Required (Yes/No): No			
CO Phasing (list CO phasing of CTR mitigations and/or TIS improvements if applicable): TBD			
1)			
2)			
3)			
4)			
5)			





REZONING PETITION
FOR PUBLIC HEARING
2026-001

MOUNT HOLLY ROAD
CHARLOTTE, NORTH CAROLINA

MISSION PROPERTIES
1114 CLEMENT AVE. #100
CHARLOTTE, NC 28205
704.307.8265

0
SCALE: N.T.S

JANUARY 15, 2026

RZ2.00

Copyright © 2026 Design Resource Group, PA This plan or drawing and any accompanying documents or calculations are the property of Design Resource Group, PA; and are intended solely for the use of the recipient noted. No third party use or modification is permitted without written authorization.

a. IF THIS REZONING PETITION IS APPROVED, ALL CONDITIONS APPLICABLE TO THE DEVELOPMENT OF THE SITE IMPOSED UNDER THE REZONING PLAN WILL, UNLESS AMENDED IN THE MANNER PROVIDED UNDER THE ORDINANCE, BE BINDING UPON AND INURE TO THE BENEFIT OF THE PETITIONER AND SUBSEQUENT OWNERS OF THE SITE AND THEIR RESPECTIVE HEIRS, DEVISEES, PERSONAL REPRESENTATIVES, SUCCESSORS IN INTEREST OR ASSIGNS.

\\SDSKPRC01\695-019 MISSION - MOUNT HOLLY ROAD\DWG\DRG - PLOT SHEETS\PLT-RZ.DWG

NOTES:

1. THIS PLAT IS NOT FOR RECORDATION AS PER G.S. 47-30 AS AMENDED.
2. ALL CORNERS MONUMENTED AS SHOWN.
3. DISTANCES SHOWN HEREON ARE HORIZONTAL GROUND DISTANCES, UNLESS OTHERWISE NOTED.
4. AREA CALCULATIONS WERE DETERMINED BY COORDINATE COMPUTATION.
5. UNDERGROUND UTILITIES MAY EXIST THAT ARE NOT SHOWN HEREON. NO GUARANTEE CAN BE MADE THAT ALL UNDERGROUND UTILITIES PRESENT, EITHER IN SERVICE OR ABANDONED, ARE SHOWN. THE LOCATION OF UNDERGROUND UTILITIES SHOWN ON THIS MAP IS APPROXIMATE, BASED ON INFORMATION PROVIDED BY OTHERS OR BY FIELD LOCATION, AS OBSERVED AT THE TIME OF THIS SURVEY. UTILITY LOCATIONS AS SHOWN HEREON ARE INTENDED FOR PLANNING ONLY. ACTUAL LOCATION, SIZE, OR DEPTH OF LINE SHOULD BE VERIFIED WITH THE INDIVIDUAL UTILITY COMPANY BEFORE CONSTRUCTION. CORNERSTONE PROFESSIONAL LAND SURVEYING IS NOT LIABLE FOR MISIDENTIFIED, MISSING, OR WRONGLY LOCATED UTILITIES.
6. BROKEN LINES, UNLESS DESCRIBED WITH A COURSE AND DISTANCE, INDICATE PROPERTY LINES NOT SURVEYED.
7. MOUNT HOLLY ROAD IS SHOWN AS A "MAJOR THOROUGHFARE" ON THE MECKLENBURG-UNION METROPOLITAN PLANNING ORGANIZATION THOROUGHFARE PLAN OF 2004 AND MAY BE SUBJECT TO A FUTURE RIGHT-OF-WAY OF 50' FROM CENTERLINE.
8. THE OFF-SITE RIGHT-OF-WAY SHOWN HEREON IS FOR ILLUSTRATIVE PURPOSES ONLY. THE UNDERSIGNED CERTIFIES ONLY TO THE RIGHT-OF-WAYS SURVEYED, AND DOES NOT CERTIFY TO THE RIGHT OF WAY WIDTH OF ANY ADJACENT PROPERTIES.
9. ELEVATIONS BASED ON N.G.S. MONUMENT "WHITE", ELEVATION = 717.70 FEET (NAVD 88).
10. (ALTA 16) AT THE TIME OF THIS SURVEY, THERE WAS NO OBSERVED EVIDENCE OF RECENT EARTH MOVING WORK, BUILDING CONSTRUCTION, OR BUILDING ADDITIONS.
11. (ALTA 17) AT THE TIME OF THIS SURVEY, THERE WAS NO OBSERVED EVIDENCE OF RECENT STREET OR SIDEWALK CONSTRUCTION OR REPAIRS. SURVEYOR IS UNAWARE OF PROPOSED CHANGES IN STREET RIGHT OF WAY LINES.
12. THIS SURVEY WAS PERFORMED WITHOUT BENEFIT OF A TITLE COMMITMENT REPORT. CORNERSTONE PROFESSIONAL LAND SURVEYING, PLLC DOES NOT CLAIM THAT ALL MATTERS OF RECORD WHICH MAY OR MAY NOT AFFECT THE SUBJECT PROPERTY ARE SHOWN HEREON.

LINE LEGEND:

EASEMENT	---
FENCE	---
PROPERTY LINE	---
PROPERTY LINE (NOT SURVEYED)	---
RIGHT-OF-WAY	---
RIGHT-OF-WAY (NOT SURVEYED)	---
FIBER OPTIC LINE	---
GAS LINE	---
POWER LINE	---
POWER LINE (UNDERGROUND)	---
SANITARY SEWER PIPE	---
STORM DRAIN PIPE	---
WATER LINE	---
WOOD FENCE	---

LEGEND:

BFP - BACK FLOW PREVENTOR
BM - BENCHMARK
C&G - CURB & GUTTER
CB - CATCH BASIN
CGF - COMBINED GRID FACTOR
CMP - CORRUGATED METAL PIPE
CP - CALCULATED POINT
CPP - CORRUGATED PLASTIC PIPE
C/L - CENTERLINE
C/O - CLEAN OUT
CONC. - CONCRETE
D.B. - DEED BOOK
DIP - DUCTILE IRON PIPE
EIP - EXISTING IRON PIPE
EIR - EXISTING IRON PIPE
EMM - EXISTING METAL MONUMENT
EN - EXISTING NAIL
EOG - EDGE OF GRAVEL
EOP - EDGE OF PAVEMENT
EU - END UNKNOWN
FFE - FINISHED FLOOR ELEVATION
FH - FIRE HYDRANT
FGB - FIBER OPTIC BOX
GM - GAS METER
GR - GRATE
GV - GAS VALVE
GW - GUY WIRE
H/VAC - HEATING, VENTILATION, AIR COND.
INV - INVERT
LP - LIGHT POLE
MBX - MAILBOX
M.B. - MAP BOOK
MH - MANHOLE
N.G.S. - NATIONAL GEODETIC SURVEY
NIR - NEW IRON ROD
NN - NEW NAIL
O/HANG - OVERHANG
PB - POWER BOX
PIN - PARCEL IDENTIFICATION NUMBER
P/L - PROPERTY LINE
PM - POWER METER
PMH - POWER MANHOLE
PP - POWER POLE
P/C - PAGE
PVC - PLASTIC PIPE
(R) - RECORDED
R/W - RIGHT-OF-WAY
RCP - REINFORCED CONCRETE PIPE
SSMH - SANITARY SEWER MANHOLE
(T) - TOTAL
TB - TELEPHONE BOX
WB - WATER BOX
WM - WATER METER
WV - WATER VALVE

TREE LEGEND:

CED - CEDAR
CRP - CREPE MYRTLE
MAP - MAPLE
PEC - PECAN

MAP REFERENCES:

- R1 - D.B. 6663, PG. 541
R2 - D.B. 6663, PG. 544
R3 - D.B. 22964, PG. 644
R4 - D.B. 6053, PG. 466
R5 - M.B. 25, PG. 59

UTILITIES:

POWER
DUKE POWER ENERGY
1-800-777-9998
TELEPHONE
BELL SOUTH TELECOMMUNICATIONS
1-888-757-6500
WATER & SEWER
CHAR.-MECK. UTILITY DEPT. (CMUD)
(704) 336-2564 WATER
(704) 357-6064 SEWER
GAS
PIEDMONT NATURAL GAS CO.
1-800-752-7504
CABLE TELEVISION
SPECTRUM
1-800-892-2253

AREA RESERVED FOR TITLE COMMITMENT:

CURVE TABLE:

LINE	BEARING	DISTANCE
L1	S48°48'00"E	7.68
L2	S40°57'44"W	20.20

ZONING:

SUBJECT PROPERTY ZONED: ML-1
ZONING RESTRICTIONS AS PER ZONING ORDINANCE:

FOR FURTHER INFORMATION CONTACT THE CHARLOTTE-MECKLENBURG ZONING DEPARTMENT AT 704-336-3569.



NOTE: NO ZONING REPORT OR ZONING VERIFICATION LETTER WAS PROVIDED TO THE SURVEYOR, PURSUANT TO ALTA TABLE A ITEM 6, PURCHASER / DEVELOPER TO VERIFY ZONING RESTRICTIONS PRIOR TO DEVELOPMENT OF THIS SITE.

FLOOD CERTIFICATION:

THIS IS TO CERTIFY THAT THE SUBJECT PROPERTY IS NOT LOCATED IN A SPECIAL FLOOD HAZARD AREA AS SHOWN ON MAPS PREPARED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY, FEDERAL INSURANCE ADMINISTRATION, DATED SEPTEMBER 2, 2015.
MAP NUMBER: 3710451600K; ZONE 'X'


OBSERVED PARKING:

THERE WERE NOT DELINEATED PARKING SPACES ON THE SUBJECT PROPERTIES AT THE TIME OF THIS SURVEY.



SURVEYOR DESCRIPTION (PIN: 053-261-09)

COMMENCING AT NGS Monument "White" having Coordinates of North: 564,987.28' and East: 1,411,954.78' North 31°17'36" West a ground distance of 2,464.45' to an existing iron rod being in the center of the existing P & N Rail Road Tracks and said point also being on the northern line of Beacon RCP, LLC as described in Deed Book 33021, Page 307, recorded in the Mecklenburg County Register of Deeds and said point also being the point of BEGINNING. Thence from said point of beginning and running with the northern line of Beacon RCP, LLC and the center of said tracks North 89°04'13" West a distance of 563.33' to an existing iron rod being on the eastern line of U.S. National Whitewater Center, Inc. as described in Deed Book 30448, Page 891; thence with the eastern line of U.S. National Whitewater Center, Inc. North 00°09'15" East a distance of 299.84' to an existing iron; thence turning and running South 86°57'48" East a distance of 310.27' to an existing iron; thence turning and running North 24°01'27" East a distance of 649.13' to an existing iron being on the southern right of way line of Mount Holly Road; thence with the southern line of Mount Holly Road South 49°09'26" East a distance of 587.81' to an existing iron; thence turning the following three (3) courses and distances:
1) South 32°27'33" West a distance of 217.99' to an existing iron;
2) South 30°39'14" West a distance of 222.38' to an existing iron pipe;
3) South 60°59'33" West a distance of 49.41' to an existing iron in the centerline of the northern rail road tracks and being the northeastern corner of aforementioned Beacon RCP, LLC, thence with the northern line of Beacon RCP, LLC South 60°52'33" West a distance of 209.20' to the POINT OF BEGINNING, having an area of 467,480 square feet, or 10.7319 acres of land as shown on a survey prepared by Cornerstone Professional Land Surveying, PLLC dated January 7, 2026 (Job Number 2025-410).



SURVEYOR DESCRIPTION (PIN: 053-261-08)

COMMENCING AT NGS Monument "White" having Coordinates of North: 564,987.28' and East: 1,411,954.78' North 15°13'03" West a ground distance of 2,533.98' to an existing iron rod being on southern right of way line of Mount Holly Road and being a northerly corner of L.A. Belk as described in Deed Book 9250, Page 469 recorded in the Mecklenburg County Register of Deeds and said point being the point of BEGINNING. Thence from said point of beginning and running with line of L.A. Belk South 40°59'49" West passing an existing iron rod at a distance of 290.06'; passing an existing iron pipe at an additional 0.33' for a total distance of 327.18' to a calculated point being in the center of the existing P & N Rail Road Tracks and said point also being on the northern line of Myrtle H. Powell as described in Deed Book 10108, Page 506; thence running with the northern line of Myrtle H. Powell and the center of said tracks with a curve turning to the left, with an arc length of 217.83', and a radius of 3,018.76' (chord: North 87°29'12" West 217.78') to an existing iron rod being on the eastern line of Edwin T. Young, Jr. and Janis R. Young as described in Deed Book 6663, Page 541 and Deed Book 6663, Page 544; thence with line of Edwin T. Young, Jr. and Janis R. Young North 60°59'33" East a distance of 49.41' to an existing iron pipe; thence turning and running North 31°03'54" East a distance of 221.39' to an existing iron pipe; thence turning and running North 32°02'07" East a distance of 199.48' to a new iron rod being on the southern right of way line of Mount Holly Road; thence with the southern line of Mount Holly Road South 49°17'55" East a distance of 222.84' to a new iron rod to the POINT OF BEGINNING, having an area of 74,318 square feet, or 1.7061 acres of land as shown on a survey prepared by Cornerstone Professional Land Surveying, PLLC dated January 7, 2026 (Job Number 2025-410).

ALTANSPS LAND TITLE SURVEY PREPARED FOR:

TO BE DETERMINED

10109 & 10039 MOUNT HOLLY ROAD
CITY OF CHARLOTTE MECKLENBURG COUNTY, NORTH CAROLINA
DEED REFERENCE: BOOK 6663, PAGE 541/544; BOOK 22964, PAGE 644
TAX PARCEL NO.: 053-261-08 AND 053-261-08

PROJECT NUMBER:

2025-410

DATE: JAN. 7, 2026 SCALE: 1" = 50'
CREW: AB/ND/ADB DRAWN: ND/BM CHECKED: AB

DRAWING REVISIONS

DATE DESCRIPTION

SHEET NUMBER:

1 OF 1