

- SITE ACREAGE: 7.68 AC  
TAX PARCELS INCLUDED IN REZONING: 03708112  
EXIST. ZONING: R-3 (LAKE WLYE PROTECTED AREA)  
PROPOSED ZONING: R-5(CD) (LAKE WLYE PROTECTED AREA)  
PROPOSED USE: SINGLE FAMILY DETACHED  
PROPOSED DENSITY: (3.78) UNITS PER ACRE  
TOTAL UNITS: 29  
OPEN SPACE (NOT INCL. PONDS): 1.3 AC (16.9%)  
MIN. TREE SAVE AREA (1.152 AC) TO BE RESERVED IN OPEN SPACE AREA  
MIN. 6000 SF FRONTAGE  
MIN. 17' FRONT YARD (LOCAL AND COLLECTOR STREETS)  
MIN. 35' REAR YARD  
MIN. 5' SIDE YARD  
MIN. 20' YARD AT THOROUGHFARE STREETS

1. Development of the site will be controlled by the standards depicted on this site plan and by the standards of the Charlotte Zoning Ordinance. The development depicted on this plan is intended to reflect the arrangement of proposed used on the site, but the exact configuration, placement, and size of individual site elements may be altered or modified within the limits prescribed by the ordinance during the design development and construction phases as allowed under the provisions of Section 6.2 of the Zoning Ordinance.

- The purpose of this Rezoning applications is to provide for the development of a residential community composed of single family detached dwellings. To achieve this purpose, the application seeks the rezoning of the site to the R-5(CD) district.

Uses allowed on this property included in this Petition will be single family detached dwelling units and related accessory uses as are permitted in the R-5(CD) District.

1. Petitioner shall dedicate in fee simple 36' right-of-way as measured from miranda road's existing centerline along the site's miranda road frontage.
2. All transportation improvements will be approved and constructed before the site's first building certificate of occupancy. Transportation improvements may be phased if said improvements and phasing are explicitly described in site plan notes.
3. Petitioner shall provide 2.5' curb/gutter, an 8' planting strip, and 6' sidewalk along the site's Miranda Rd. frontage.
4. Petitioner shall provide dedication and fee simple conveyance of all rights of way to the City before the site's first building certificate of occupancy is issued. CDOT requests right of way set at 2' behind back of sidewalk where feasible.
5. Per contact with NCDOT, a westbound left turn storage lane is not required at the subdivision entrance.
6. The main entrance road connecting to Miranda Road shall be a Local Collector Street per the typical section.
7. According to the City of Charlotte's Driveway Regulations, CDOT has the authority to regulate/approve all private street/driveway and public street connections to the right-of-way of a street under the regulatory jurisdiction of the City of Charlotte.
8. Adequate sight triangles must be reserved at the existing/proposed street entrance(s). Two 35' x 35' sight triangles (and two 10' x 70' sight triangles on North Carolina Department of Transportation on NCDOT maintained streets) are required for the entrance(s) to meet requirements. All proposed trees, berms, walls, fences, and/or identification signs must not interfere with sight distance at the entrance(s). Such items should be identified on the site plan.
9. The proposed driveway connection(s) to public streets will require a driveway permit(s) to be submitted to CDOT (and the North Carolina Department of Transportation on NCDOT maintained streets) for review and approval. The exact driveway location(s) and type/width of the driveway(s) will be determined by CDOT during the driveway permit process. The location(s) of the driveway(s) shown on the site plan are subject to change in order to align with driveway(s) on the opposite side of the street and comply with City Driveway Regulations and the City Tree Ordinance.
10. All proposed commercial driveway connections to a future public street will require a driveway permit to be submitted to CDOT for review and approval.
11. Any fence or wall constructed along or adjacent to any sidewalk or street right-of-way requires a certificate issued by CDOT.
12. A Right-of-Way Encroachment Agreement is required for the installation of any non-standard item(s) (irrigation systems, decorative concrete pavement, brick pavers, etc.) within a proposed/existing City maintained street right-of-way by a private individual, group, business, or homeowner's/business/association. An encroachment agreement must be approved by CDOT prior to the construction/installation of the non-standard item(s). Contact CDOT for additional information concerning cost, submittal, and liability insurance coverage requirements.

The development of the site will be governed by the District Regulations of the Zoning Ordinance for the R-5 district.

Streetscape and Landscaping shall be in accordance with the City of Charlotte Ordinance Standards and per the noted fencing and landscaping as shown on the Plan.

1. The petitioner shall analyze the adequacy of the existing stormwater conveyance across the adjoining parcels receiving stormwater discharge from the site. If the existing stormwater conveyance on the specified off-site parcels is found to be inadequate, the petitioner shall make a good faith effort with the property owner(s) to improve the stormwater conveyance or otherwise mitigate the stormwater discharge onto the parcel(s).

2. A tree survey shall be submitted to the city arborist for approval prior to construction.

3. The location, size, and type of storm water management systems depicted on the rezoning plan are subject to review and approval as part of the full development plan submittal and are not implicitly approved with this rezoning. Adjustments may be necessary in order to accommodate actual storm water treatment requirements and natural site discharge points.

4. Min. 15% tree save area will be required.

5. Erosion control submission will be required.



- Minimum of 15% Open Space as per the City of Charlotte Zoning Ordinance will be provided

- 10.) Fire Protection
- Fire truck turnaround at end of streets will be provided.

- 11.) Signage
- Per City of Charlotte Ordinance requirements

- Per City of Charlotte Ordinance requirements

- N/A

[illegible]