

VICINITY MAP
NTS

SITE DEVELOPMENT DATA

SITE AREA: ±8.5 ACRES

TAX PARCELS: 029-341-03 AND 029-341-04

EXISTING ZONING: R-4

PROPOSED ZONING: R - 8MF

EXISTING USES: RESIDENTIAL/VACANT

PROPOSED USES: SINGLE-FAMILY RESIDENTIAL

KEY MAP

SEAL

NOT FOR
CONSTRUCTION

PROJECT

POLK AND WHITE
SINGLE FAMILY

CHARLOTTE, NC
REZONING PETITION
#2019-157

LANDDESIGN PROJ.# 1019311


REVISION / ISSUANCE

NO.	DESCRIPTION	DATE
1	INITIAL SUBMITTAL	10.03.19
2	PER CITY COMMENTS	01.13.2020

DESIGNED BY: JRY
DRAWN BY: EHK
CHECKED BY: FJM

SCALE

VERT: N/A
HORZ: 1"=50'




SHEET TITLE

TECHNICAL DATA SHEET

SHEET NUMBER

RZ-1



PROPERTY LINE

PROPOSED PUBLIC STREET

DEVELOPMENT AREAS

PROPOSED R/W

PROPOSED SETBACK

Diagram illustrating a standard lot with various property lines and setbacks. The lot is divided into a grid of 10 columns and 10 rows. The top row is labeled 'PROPERTY LINE'. The second row is labeled 'PROPOSED PUBLIC STREET'. The third row is labeled 'DEVELOPMENT AREAS'. The fourth row is labeled 'PROPOSED R/W'. The bottom row is labeled 'PROPOSED SETBACK'. The lot is divided into a grid of 10 columns and 10 rows. The top row is labeled 'PROPERTY LINE'. The second row is labeled 'PROPOSED PUBLIC STREET'. The third row is labeled 'DEVELOPMENT AREAS'. The fourth row is labeled 'PROPOSED R/W'. The bottom row is labeled 'PROPOSED SETBACK'.

KEY MAP

SEAL

**NOT FOR
CONSTRUCTION**

PROJECT

**POLK AND WHITE
SINGLE FAMILY**

CHARLOTTE, NC
REZONING PETITION
#2019-157

LANDDESIGN PROJ.# 1019311


REVISION / ISSUANCE

[illegible]

DESIGNED BY: JRY
DRAWN BY: EHK
CHECKED BY: FJM

SCALE NORTH

VERT: N/A
HORZ: 1"=50'



0 25' 50' 100'

SHEET TITLE

SCHEMATIC SITE DATA

SHEET NUMBER

RZ-2

DEVELOPMENT STANDARDS
(JANUARY 13, 2020)

A. General Provisions

- These Development Standards form a part of the Rezoning Plan associated with the Rezoning Petition filed by ABP Development LLC to accommodate the development of a residential community on that approximately 8.5 acre site located on the south side of Polk and White Road, between Hattie Little Street and Mallard Creek Road, which site is more particularly depicted on the Rezoning Plan (the "Site"). The Site is comprised of Tax Parcel Nos. 029-341-04 and 029-341-03.
- The development of the Site will be governed by the Rezoning Plan, these Development Standards and the applicable provisions of the City of Charlotte Zoning Ordinance (the "Ordinance").
- Unless the Rezoning Plan or these Development Standards establish more stringent standards, the regulations established under the Ordinance for the R-8 MF zoning district shall govern the development and use of the Site.
- The development depicted on the Rezoning Plan is schematic in nature and intended to depict the general arrangement of uses and improvements on the Site. Accordingly, the configurations, placements and sizes of the internal public streets, internal private drives and/or alleys depicted on the Rezoning Plan are schematic in nature and, subject to the terms of these Development Standards and the Ordinance, are subject to minor alterations or modifications during the design development and construction document phases.
- The Site is divided into three separate development areas on the Rezoning Plan designated as Development Area A, Development Area B and Development Area C. The dwelling units referenced below under Permitted Uses and any accessory structures and uses shall be located within the development areas. Additionally, public streets, private drives and/or alleys and open space/tree save areas may be located in the development areas.
- In the event that it is determined that Public Street A is not required to extend to the southern boundary line of the Site, then any public right of way for Public Street A that is not required may be located within Development Area B or Development Area C.
- Future amendments to the Rezoning Plan and/or these Development Standards may be applied for by the then owner or owners of the Site in accordance with the provisions of Section 6.207 of the Ordinance.

B. Permitted Uses/Development Limitations

- The Site may be devoted only to a residential community containing a maximum of 68 dwelling units and to any incidental and accessory uses relating thereto that are allowed in the R-8 MF zoning district.
- The dwelling units may only be comprised of single family detached dwelling units, single family attached dwelling units or a combination thereof.
- The building setback from a public street shall be 17 feet for single family detached dwelling units and 27 feet for single family attached dwelling units as prescribed by the Ordinance. The types of dwelling units to be constructed on the site shall be determined during the permitting process and the applicable building setbacks shall be determined at that time.

C. Transportation

- Vehicular access to the Site shall be as generally depicted on the Rezoning Plan. The placement and configuration of the vehicular access points are subject to any minor modifications required to accommodate final site and construction plans and designs and to any adjustments required for approval by the Charlotte Department of Transportation.
- The Site will be served by internal public streets and may also be served by internal private drives and/or alleys. Minor adjustments to the locations of the internal public streets and the internal private drives and/or alleys shall be allowed during the construction permitting process.
- Petitioner shall dedicate and convey in fee simple to the City all relevant right of way prior to the issuance of the first certificate of occupancy for a new dwelling unit constructed on the Site. Right of way shall be set at 2 feet behind the back of sidewalk where feasible.
- All transportation improvements will be approved and constructed prior to the issuance of the first certificate of occupancy for a new dwelling unit constructed on the Site.

D. Architectural Standards

- The maximum height in feet of the dwelling units to be located on the Site shall be 48 feet (as measured under the Ordinance). Building height increases above 48 feet shall not be permitted.
- The primary exterior building materials for the dwelling units to be constructed on the Site will be a combination of portions of the following: brick veneer or similar masonry products, stone, manufactured stone, stucco and cementitious siding.
- Vinyl, EIFS or masonite may not be used as an exterior building material on any dwelling unit to be constructed on the Site. Notwithstanding the foregoing, vinyl may be utilized on windows, doors, garage doors, soffits, trim and railings.

E. Streetscape and Landscaping

- A minimum 8 foot wide planting strip and a minimum 6 foot wide sidewalk shall be installed along the Site's public street frontages including the Site's frontage along Polk and White Road.

F. Lighting

- All freestanding lighting fixtures installed on the Site (excluding lower, decorative lighting that may be installed along the driveways and sidewalks and landscaping lighting) shall be fully capped and shielded and the illumination downwardly directed so that direct illumination does not extend past any property line of the Site.
- The maximum height of any freestanding lighting fixtures installed on the Site, excluding street lights located along public streets, shall be 21 feet.

G. Environmental

- The Petitioner shall comply with the Charlotte City Council approved and adopted Post Construction Controls Ordinance.
- Development of the Site shall comply with the Tree Ordinance.

H. Binding Effect of the Rezoning Documents and Definitions

- If this Rezoning Petition is approved, all conditions applicable to the use and development of the Site imposed under these Development Standards and the Rezoning Plan will, unless amended in the manner provided under the Ordinance, be binding upon and inure to the benefit of Petitioner and the current and subsequent owners of the Site and their respective successors in interest and assigns.
- Throughout these Development Standards, the term "Petitioner" shall be deemed to include the heirs, devisees, personal representatives, successors in interest and assigns of Petitioner or the owner or owners of the Site from time to time who may be involved in any future development thereof.
- Any reference to the Ordinance herein shall be deemed to refer to the requirements of the Ordinance in effect as of the date this Rezoning Petition is approved.

KEY MAP

SEAL

NOT FOR
CONSTRUCTION

PROJECT

POLK AND WHITE
SINGLE FAMILY

CHARLOTTE, NC
REZONING PETITION
#2019-157

LANDDESIGN PROJ.# 1019311

REVISION / ISSUANCE		
NO.	DESCRIPTION	DATE
1	INITIAL SUBMITTAL	10.03.19
2	PER CITY COMMENTS	01.13.2020

DESIGNED BY: JRY
DRAWN BY: EHK
CHECKED BY: FJM

SCALE NORTH
VERT: N/A
HORZ: 1"= 50'
0 25' 50' 100'

SHEET TITLE

DEVELOPMENT STANDARDS

SHEET NUMBER

RZ-3